

CASE STUDY

BEESTON REGIS UWC VAMOS UPGRADE



RCU was contracted to undertake the E&P / Signalling element of Beeston Regis UWC upgrade which included:

- Install 1700m of SWA Power Cable
- Install VaMoS Equipment (1x VaMoS Control Cubicle, 2x Pole's, 3x GAK's and 3x Wheel Sensor's)
- Build and Install CCTV LOC
- Install and terminate all associated cables
- Install 1x CMS Sleeper (Metal Hollow Sleeper)
- Install Earth Pot and Rods



**EXPERTISE:
E&P
SIGNALLING**



CLIENT:

AMCO GIFFEN



**VALUE:
£45,000**



**DURATION:
FEB 2020 TO
MARCH 2020**



RAIL



CONSTRUCTION



UTILITIES